

Cambois Connection – Onshore Scheme
Environmental Statement Volume 3
Technical Appendix 13.2: Construction Plant
Sound Levels







Cambois Connection Onshore Scheme

Technical Appendix 13.2: Construction Plant Sound Levels

SSE Renewables

Prepared by:

SLR Consulting Limited

Studio 305, Maling Exchange, Hoults Yard, Walker Road, Newcastle upon Tyne, NE6 2HL

SLR Project No.: 404.000041.00001

29 October 2023

Revision: A01

Revision Record

Revision	Date	Prepared By	Checked By	Authorised By
R01	25 May 2023	Jon Munns	Susie Playford	Susie Playford
A01	28 October 2023	Jack Hughes	Jon Munns	Susie Playford

Basis of Report

This document has been prepared by SLR Consulting Limited (SLR) with reasonable skill, care and diligence, and taking account of the timescales and resources devoted to it by agreement with SSE Renewables (the Client) as part or all of the services it has been appointed by the Client to carry out. It is subject to the terms and conditions of that appointment.

SLR shall not be liable for the use of or reliance on any information, advice, recommendations and opinions in this document for any purpose by any person other than the Client. Reliance may be granted to a third party only in the event that SLR and the third party have executed a reliance agreement or collateral warranty.

Information reported herein may be based on the interpretation of public domain data collected by SLR, and/or information supplied by the Client and/or its other advisors and associates. These data have been accepted in good faith as being accurate and valid.

The copyright and intellectual property in all drawings, reports, specifications, bills of quantities, calculations and other information set out in this report remain vested in SLR unless the terms of appointment state otherwise.

This document may contain information of a specialised and/or highly technical nature and the Client is advised to seek clarification on any elements which may be unclear to it.

Information, advice, recommendations and opinions in this document should only be relied upon in the context of the whole document and any documents referenced explicitly herein and should then only be used within the context of the appointment.

i



Table of Contents

Bas	is of Reporti
1.0	Construction Phases4
2.0	Sound Power Levels Per Phase4
Ta	bles in Text
Tab	le A: Combined sound power levels – construction plant for landfall and onshore ECC, dB4
Tab	le B: Combined sound power levels – construction plant for substation options, dB 4
Tab	le C: Plant utilised in construction phase – Establish Access and Temporary Construction Compound (including Trenchless Drilling compounds)5
Tab	le D: Plant utilised in construction phase – Site Preparation, Including Fencing, Haul Road Construction and Topsoil Strip6
Tab	le E: Plant utilised in construction phase – Transition Joint Bay Excavation
Tab	le F: Plant utilised in construction phase – Transition Bay Wall and Base Construction 8
Tab	le G: Plant utilised in construction phase – Connection of Cables in Transition Bays 8
Tab	le H: Plant utilised in construction phase – Roof and Backfill over Transition Joint Bay 9
Tab	le I: Plant utilised in construction phase – Trench Excavation and Duct Installation 10
Tab	le J: Plant utilised in construction phase – Trench Backfill11
Tab	le K: Plant utilised in construction phase – Joint Bay Excavation
Tab	le L: Plant utilised in construction phase – Jointing Bay Base Construction
Tab	le M: Plant utilised in construction phase – Pulling and Connection of Cables
Tab	le N: Plant utilised in construction phase – Backfill over Jointing Bay13
Tab	le O: Plant utilised in construction phase – Trench Route Reinstatement / Topsoil Reinstatement14
Tab	le P: Plant utilised in construction phase – Haul Road Removal and Removal of Fencing and Reinstatement15
Tab	le Q: Plant utilised in construction phase – Temporary Construction Compound and Access Road Removal (including Trenchless Drilling compounds)
Tab	le R: Plant utilised in construction phase – Landfall Operations16
Tab	le S: Plant utilised in construction phase – Unlicenced Works (Assumed Plant Requirements)
Tab	le T: Plant utilised in construction phase – Temporary Construction Compound Operations17
Tab	le U: Plant utilised in Trenchless Crossing Compound Operations – Daytime18
	le V: Plant utilised in Trenchless Crossing Compound Operations – Night-Time (where applicable)
Tab	le W: Plant utilised in substation construction phase – Groundworks19
Tab	le X: Plant utilised in substation construction phase – Building foundation works 19



Table Y: Plant utilised in substation construction phase – Access road and car proad works	•
Table Z: Plant utilised in substation construction phase – Building fabrication ar Installation	



1.0 Construction Phases

This appendix contains a list of indicative plant based on professional judgement gained from experience of similar developments that are at a further stage of development. Based on this list, the combined sound power level (SWL), measured in decibels (dB), has been calculated for each construction activity considering the number of plant and associated ontimes, as shown in Table A and Table B.

Table A: Combined sound power levels - construction plant for landfall and onshore ECC, dB

Activity	Combined Sound Power Level (SWL), dB
1. Establish Access and TCC (including trenchless drilling compounds)	120
2. Site Preparation, Including Fencing, Haul Road Construction and Topsoil Strip	120
3. Transition Joint Bay Excavation	116
4. Transition Joint Bay Wall and Base Construction	114
5. Connection of Cables in Transition Bays	115
6. Roof and Backfill over Transition Bay	118
7. Trench Excavation and duct installation	118
8. Trench Backfill	119
9. Joint Bay Excavation	116
10. Joint Bay Base Construction	114
11. Pulling and Connection of Cables	114
12. Backfill over Joint Bay	118
13. TCC Operations	109
14. Trenchless Drilling Compound Operations (including piling)	116

Table B: Combined sound power levels - construction plant for substation options, dB

Activity	Combined Sound Power Level (SWL), dB
1. Ground Works	123
2. Building Foundation	119
3. Access Road and Carparks	116
4. Building Fabric and High Voltage Plant	118

2.0 Sound Power Levels Per Phase

Table C to Table Z outline the plant that may be used in each construction phase of the development, including the sound power level of each item of plant, the number that is anticipated, the percentage on time of these, and the resultant sound power level of the plant.

It should be noted that these are reasonable worst-case scenarios for the types and number of plant – during detailed design, as the construction methodology is finalised, there is potential for these plant lists to be refined further.



29 October 2023

29 October 2023 Cambois Connection Onshore Scheme SLR Project No.: 404.000041.00001

Table C: Plant utilised in construction phase – Establish Access and Temporary Construction Compound (including Trenchless Drilling compounds)

Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)
D6 Dozer	109	1	100	109
30T excavator	103	2	100	106
20T Dumper	109	3	100	114
Smooth Drum vibro road roller	103	1	100	103
21T excavator	106	1	100	106
5T Forward Tipping Dumper	106	1	100	106
Loading shovel	108	1	100	108
Tractor & fencing kit	108	1	100	108
Tractor & trailer	107	1	70	105
Tractor & Fuel bowser (or self-propelled)	117	1	10	107
Tractor & Water bowser (for dust suppression)	111	1	25	105
Grader	114	1	100	114
Telehandler	107	1	70	105
Mobile self-contained welfare unit	94	1	25	88
Mobile generator	102	2	25	99
Temporary lighting	93	6	50	98
Road surface paver & roller	112	1	25	106
Logarithmic sum				120



Table D: Plant utilised in construction phase – Site Preparation, Including Fencing, Haul Road
Construction and Topsoil Strip

	Construction and Topson Strip						
Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)			
D6 Dozer	109	1	100	109			
30T excavator	103	2	100	106			
20T Dumper	109	3	100	114			
Smooth Drum vibro road roller	103	1	100	103			
21T excavator	106	1	100	106			
5T Forward Tipping Dumper	106	1	100	106			
Loading shovel	108	1	100	108			
Tractor & fencing kit	108	1	100	108			
Tractor & trailer	107	1	70	105			
Tractor & Fuel bowser (or self-propelled)	117	1	10	107			
Tractor & Water bowser (for dust suppression)	111	1	25	105			
Grader	114	1	100	114			
Telehandler	107	1	70	105			
Mobile self-contained welfare unit	94	1	25	88			
Mobile generator	102	2	25	99			
Temporary lighting	93	12	25	98			
Logarithmic sum	120						



onnection Onshore Scheme SLR Project No.: 404.000041.00001

Table E: Plant utilised in construction phase – Transition Joint Bay Excavation

Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)
30T excavator	103	1	100	103
20T Dumper	109	2	100	112
Smooth Drum vibro roller	103	1	10	93
21T excavator	106	1	50	103
5T Forward Tipping Dumper	106	1	50	103
Tractor & Fuel bowser (or self-propelled)	117	1	10	107
Tractor & Water bowser (for dust suppression)	111	1	25	105
Mobile self-contained welfare unit	94	1	25	88
Mobile generator	102	2	25	99
Temporary lighting	93	4	25	93
Pump	106	2	100	109
Piling Rig	116	1	10	106
Logarithmic sum				116



29 October 2023 SLR Project No.: 404.000041.00001

Table F: Plant utilised in construction phase – Transition Bay Wall and Base Construction

Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)
Tractor & trailer	107	1	50	104
Tractor & Fuel bowser (or self-propelled)	117	1	10	107
Tractor & Water bowser (for dust suppression)	111	1	25	105
Mobile concrete pump / concrete mixer truck	108	1	50	105
Telehandler	107	1	50	104
Mobile self-contained welfare unit	94	1	25	88
Mobile generator	102	2	50	102
Temporary lighting	93	4	25	93
Pump	106	2	100	109
Logarithmic sum		114		

Table G: Plant utilised in construction phase - Connection of Cables in Transition Bays

Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)
Tractor & trailer	107	1	50	104
Tractor & Fuel bowser (or self-propelled)	117	1	10	107
Tractor & Water bowser (for dust suppression)	111	1	25	105
Mobile crane	110	1	25	104
Cable laying tracked crane	103	1	25	97
Telehandler	107	1	50	104
Mobile self-contained welfare unit	94	1	20	87
Crawler Crane	103	1	25	97
Mobile generator	102	2	100	105
Temporary lighting	93	4	50	96
Pump	106	2	100	109
Logarithmic sum		115		



Table H: Plant utilised in construction phase – Roof and Backfill over Transition Joint Bay

Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)
D6 Dozer	109	1	100	109
30T excavator	103	1	100	103
20T Dumper	109	2	100	112
21T excavator	106	1	100	106
5T Forward Tipping Dumper	106	1	100	106
Loading shovel	108	1	100	108
Trench Roller	101	1	75	100
Tractor & trailer	107	1	25	101
Tractor & Fuel bowser (or self-propelled)	117	1	10	107
Tractor & Water bowser (for dust suppression)	111	1	25	105
Cement mixer	89	1	25	83
Mobile crane	110	1	25	104
Pre-cast concrete truck	111	1	5	98
Telehandler	107	1	25	101
Mobile self-contained welfare unit	94	1	25	88
Mobile generator	102	2	25	99
Temporary lighting	93	4	25	93
Pump	106	2	100	109
Logarithmic sum				118



Table I: Plant utilised in construction phase – Trench Excavation and Duct Installation

		•			
Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)	
30T excavator	103	2	100	106	
20T Dumper	109	2	100	112	
21T excavator	106	2	100	109	
5T Forward Tipping Dumper	106	2	100	109	
Loading shovel	108	2	50	108	
Trench Roller	101	2	50	101	
Tractor & trailer	107	1	50	104	
Tractor & Fuel bowser (or self-propelled)	117	1	10	107	
Tractor & Water bowser (for dust suppression)	111	1	25	105	
Telehandler	107	1	50	104	
Mobile self-contained welfare unit	94	1	25	88	
Crawler Crane	103	1	10	93	
Mobile generator	102	2	25	99	
Temporary lighting	93	8	25	96	
Pump	106	2	100	109	
Logarithmic sum	•			118	



Table J: Plant utilised in construction phase – Trench Backfill

	rable of Flank atmood in conciliation phase Tronon Backing				
Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)	
30T excavator	103	2	100	106	
20T Dumper	109	2	100	112	
21T excavator	106	2	100	109	
5T Forward Tipping Dumper	106	2	100	109	
Loading shovel	108	2	100	111	
Trench Roller	101	2	75	103	
Tractor & trailer	107	1	25	101	
Tractor & Fuel bowser (or self-propelled)	117	1	10	107	
Tractor & Water bowser (for dust suppression)	111	1	25	105	
Telehandler	107	1	25	101	
Mobile self-contained welfare unit	94	1	25	88	
Mobile generator	102	2	25	99	
Temporary lighting	93	8	25	96	
Pump	106	2	100	109	
Logarithmic sum	•		•	119	



29 October 2023 SLR Project No.: 404.00041.00001

Table K: Plant utilised in construction phase - Joint Bay Excavation

Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)	
30T excavator	103	2	100	106	
20T Dumper	109	2	100	112	
Smooth drum vibro roller	103	1	10	93	
21T excavator	106	1	50	103	
5T Forward Tipping Dumper	106	1	50	103	
Tractor & Fuel bowser (or self-propelled)	117	1	10	107	
Tractor & Water bowser (for dust suppression)	111	1	25	105	
Mobile self-contained welfare unit	94	1	25	88	
Mobile generator	102	2	25	99	
Temporary lighting	93	4	25	93	
Pump	106	2	100	109	
Logarithmic sum	Logarithmic sum				

Table L: Plant utilised in construction phase – Jointing Bay Base Construction

Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)	
Tractor & trailer	107	1	50	104	
Tractor & Fuel bowser (or self-propelled)	117	1	10	107	
Tractor & Water bowser (for dust suppression)	111	1	25	105	
Mobile concrete pump / cement mixer truck	108	1	50	105	
Telehandler	107	1	50	104	
Mobile self-contained welfare unit	94	1	25	88	
Mobile generator	102	2	50	102	
Temporary lighting	93	4	25	93	
Pump	106	2	100	109	
Logarithmic sum	Logarithmic sum				



29 October 2023 SLR Project No.: 404.000041.00001

Table M: Plant utilised in construction phase - Pulling and Connection of Cables

Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)
Tractor & Fuel bowser (or self-propelled)	117	1	10	107
Tractor & cable drum trailer	108	1	50	105
Cable winch	111	1	50	108
Mobile self-contained welfare unit	94	1	25	88
Mobile generator	102	2	25	99
Temporary lighting	93	4	25	93
Pump	106	2	100	109
Logarithmic sum				114

Table N: Plant utilised in construction phase - Backfill over Jointing Bay

Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)
D6 Dozer	109	2	100	112
30T excavator	103	2	100	106
20T Dumper	109	2	100	112
21T excavator	106	1	100	106
5T Forward Tipping Dumper	106	1	100	106
Loading shovel	108	1	100	108
Trench Roller	101	1	75	100
Tractor & Fuel bowser (or self-propelled)	117	1	10	107
Tractor & Water bowser (for dust suppression)	111	1	25	105
Mobile self-contained welfare unit	94	1	25	88
Mobile generator	102	2	25	99
Temporary lighting	93	4	25	93
Pump	106	2	100	109
Logarithmic sum	•			118



29 October 2023 ore Scheme SLR Project No.: 404.000041.00001

Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)
D6 Dozer	109	2	100	112
30T excavator	103	2	100	106
20T Dumper	109	2	100	112
Smooth Drum vibro roller	103	1	50	100
21T excavator	106	1	100	106
5T Forward Tipping Dumper	106	1	100	106
Loading shovel	108	2	100	111
Tractor & Fuel bowser (or self-propelled)	117	1	10	107
Tractor & Water bowser (for dust suppression)	111	1	25	105
Mobile self-contained welfare unit	94	1	25	88
Mobile generator	102	2	25	99
Temporary lighting	93	8	25	96
Logarithmic sum				118

Table O: Plant utilised in construction phase – Trench Route Reinstatement / Topsoil



Logarithmic sum

mbois Connection Onshore Scheme SLR Project No.: 404.000041.00001

Table P: Plant utilised in construction phase - Haul Road Removal and Removal of Fencing

and Reinstatement Vehicle / Equipment Sound Indicative Estimated Resultant Power Percentage of Number **Sound Power** Level, dB(A) Operation During Level, dB(A) **Activity** D6 Dozer 30T excavator 20T Dumper Smooth Drum vibro roller 21T excavator **5T Forward Tipping** Dumper Loading shovel Tractor & fencing kit Tractor & trailer Tractor & Fuel bowser (or self-propelled) Tractor & Water bowser (for dust suppression) Tractor & soil tiller, roller, seeder Mobile self-contained welfare unit Mobile generator Temporary lighting



29 October 2023 SLR Project No.: 404.000041.00001

Table Q: Plant utilised in construction phase – Temporary Construction Compound and Access Road Removal (including Trenchless Drilling compounds)

Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)
D6 Dozer	109	2	100	112
30T excavator	103	2	100	106
20T Dumper	109	2	100	112
Smooth Drum vibro roller	103	1	50	100
21T excavator	106	1	100	106
5T Forward Tipping Dumper	106	1	100	106
Loading shovel	108	2	100	111
Tractor & fencing kit	108	1	50	105
Tractor & trailer	107	1	50	104
Tractor & Fuel bowser (or self-propelled)	117	1	10	107
Tractor & Water bowser (for dust suppression)	111	1	25	105
Tractor & soil tiller, roller, seeder	108	1	25	102
Mobile self-contained welfare unit	94	2	25	91
Mobile generator	102	2	25	99
Temporary lighting	93	6	25	95
Logarithmic sum				119

Table R: Plant utilised in construction phase - Landfall Operations

Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)
21T excavator	106	1	10	96
Cable winch	111	1	10	101
Temporary lighting	93	4	25	93
Pump	106	2	50	106
Logarithmic sum	108			



Connection Onshore Scheme SLR Project No.: 404.000041.00001

Table S: Plant utilised in construction phase – Unlicenced Works (Assumed Plant Requirements)

Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)
21T excavator	106	1	25	100
5T Forward Tipping Dumper	106	1	25	100
Trench Roller	101	1	10	91
Mobile crane	110	1	25	104
Mobile generator	102	1	25	96
Temporary lighting	93	1	25	87
Pump	106	1	25	100
Logarithmic sum		108		

Table T: Plant utilised in construction phase – Temporary Construction Compound Operations

		•	•	•
Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)
Generator	102	2	100	105
Telehandler	107	1	75	106
Road Sweeper	104	1	10	94
Logarithmic sum				109



nection Onshore Scheme SLR Project No.: 404.000041.00001

Table U: Plant utilised in Trenchless Crossing Compound Operations - Daytime

Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)
Generator	102	1	100	102
Telehandler	107	2	75	109
Vibratory Piling Rig	116	1	10	106
Directional Drill Generator	105	1	100	105
Mounting supports for directional drill (hydraulic hammer)	115	1	25	109
Mud Pump	108	1	100	108
Mixing Tank	103	1	100	103
Cuttings / Recycling Tank	108	1	100	108
Logarithmic sum				116

Table V: Plant utilised in Trenchless Crossing Compound Operations – Night-Time (where applicable)

Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)
Generator	102	1	100	102
Telehandler	107	2	75	109
Directional Drill Generator	105	1	100	105
Mud Pump	108	1	100	108
Mixing Tank	103	1	100	103
Cuttings / Recycling Tank	108	1	100	108
Logarithmic sum	114			



29 October 2023 SLR Project No.: 404.000041.00001

Table W: Plant utilised in substation construction phase - Groundworks

Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)
Excavator (earthworks)	102	6	100	110
Excavator (hydraulic breaker)	113	4	100	119
Dozer	107	4	75	112
Air compressor	100	4	100	106
Dump truck	105	8	70	112
Generator	100	2	100	103
Crusher	116	2	80	118
Logarithmic sum				123

Table X: Plant utilised in substation construction phase – Building foundation works

Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)
Percussive piling rig	116	1	100	116
Tracked drilling rig with hydraulic drifter	82	1	100	82
Crane mounted auger	79	1	100	79
Mini piling rig	76	2	100	79
Compressor for mini piling	75	1	100	75
Dump truck	105	4	50	108
Truck mixer with pump	103	2	10	96
Excavator (earthworks)	102	3	80	106
Grinder	108	5	50	112
Compressor	100	2	100	103
Generator	100	2	100	103
Logarithmic sum	<u> </u>			119



Table Y: Plant utilised in substation construction phase – Access road and car parking works

road works

Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)
Excavator	102	2	100	105
Dump truck	105	4	70	109
Asphalt spreader with support lorry	106	1	100	106
Vibratory roller	106	2	70	107
Grader	112	1	100	112
Logarithmic sum				116

Table Z: Plant utilised in substation construction phase – Building fabrication and HV Plant Installation

Vehicle / Equipment	Sound Power Level, dB(A)	Indicative Number	Estimated Percentage of Operation During Activity	Resultant Sound Power Level, dB(A)
Mobile crane	102	1	50	99
Lorry	103	3	25	102
MEWP	78	2	75	80
Dump truck	105	4	10	101
Compressor	100	1	100	100
Forklift truck	105	2	50	105
Grinder	108	5	50	112
Pneumatic chipper/drill	114	3	50	116
Scaffolding	100	1	25	94
Logarithmic sum				118



29 October 2023

